City of Pahokee - Department of Community & Economic Development
Reconstruction of Barfield Highway
FDOT FM# 441030-1-54-01
ITB NO. 2020-07
BID FORM

Pay Item	Description	Unit	Qty.	Unit Cost	Sub-Total
0101- 1-	MOBILIZATION	LS	1.00		
0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.00		
0102- 2- 1	SPECIAL DETOUR 1	LS	1.00		
0102- 2-200	SPECIAL DETOUR, TEMPORARY PAVEMENT	LS	1.00		
0102- 2-300	SPECIAL DETOUR, TEMPORARY EARTHWORK	LS	1.00		
0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	200.00		
0102- 14-	TRAFFIC CONTROL OFFICER	HR	100.00		
0102- 60-	WORK ZONE SIGN	ED	21200.00		
0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	79500.00		
0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1590.00		
0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	3595.00		
0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	300.00		
0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1060.00		
0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	265.00		
0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	265.00		
0104- 10- 3	SEDIMENT BARRIER	LF	7757.00		
0104- 11-	FLOATING TURBIDITY BARRIER	LF	287.00		
0104- 18-	INLET PROTECTION SYSTEM	EA	50.00		
0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING	LS	1.00		
0108- 2-	MONITOR EXISTING STRUCTURES - VIBRATION MONITORING	LS	1.00		
0110- 1- 1	CLEARING & GRUBBING	AC	6.12		
0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2611.00		
0110- 7- 1	MAILBOX, F&I SINGLE	EA	52.00		
0120- 1-	REGULAR EXCAVATION	CY	4857.00		
0120- 6-	EMBANKMENT	CY	3277.00		
0125- 3-	SELECT BEDDING MATERIAL	CY	2500.00		
0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	14922.00		
0160- 4-	TYPE B STABILIZATION	SY	17067.00		
0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	6652.00		
0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	14922.00		
0334- 1- 12	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B	TN	1199.50		
0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, PG 76-22	TN	1202.50		
0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	17.50		
0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	90.00		
0400- 2- 2	CONCRETE CLASS II, ENDWALLS	CY	40.00		
0415- 1- 3	REINFORCING STEEL, RETAINING WALL	LB	7190.00		
0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.00		
0425- 1-351	INLETS, CURB TYPE P-5, <10'	EA	16.00		
0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	10.00		
0425- 1-451	INLETS, CURB TYPE J-5, <10'	EA	5.00		
0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	3.00		
0425- 1-531	INLETS, DT BOTTOM, TYPE C MOD-BACK OF SIDEWALK, <10'	EA	8.00		
0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	1.00		
0425- 2- 71	MANHOLES, J-7, <10'	EA	1.00		
0425- 2- 92	MANHOLES, J-8, >10'	EA	1.00		
0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	13.00		

0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	1368.00		
0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	1273.00		
0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	1546.00		
0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	407.00		
0430-175-184	PIPE CULVERT, OPT MATERIAL, ROUND, 84"S/CD	LF	56.00		
0430-175-218	PIPE CULVERT, OPT MATERIAL,OTHER/ELLIPTICAL, 18"S/CD	LF	111.00		
0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY, 42" TYPE 1	LF	255.00		
0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	9566.00		
0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	4874.00		
0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1742.00		
0527- 2-	DETECTABLE WARNINGS	SF	294.00		
0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	240.00		
0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	94.00		
0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST	EA	40.00		
0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING END ANCHORAGE	EA	2.00		
0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.00		
0570- 1- 2	PERFORMANCE TURF, SOD	SY	12000.00		
0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.00		
0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	100.00		
0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	10.00		
0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	32.00		
0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	4.00		
0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	16.00		
0705- 10- 1	OBJECT MARKER, TYPE 1	EA	15.00		
0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1.00		
0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	899.00		
0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	232.00		
0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	294.00		
0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.67		
1050 16002	UTILITY PIPE, REMOVE & DISPOSE, 2 - 4.9"	LF	300.00		
1050 16003	UTILITY PIPE, REMOVE & DISPOSE, 5-7.9"	LF	4474.00		
1050 16004	UTILITY PIPE, REMOVE & DISPOSE, 8-19.9"	LF	251.00		
1050 31208	UTILITY PIPE, F&I, PVC, WATER / SEWER, 8"	LF	900.00		
1050 31212	UTILITY PIPE, F&I, PVC, WATER / SEWER, 12"	LF	3905.00		
1050 51206	UTILITY PIPE, F&I, DI/CI, WATER / SEWER, 6"	LF	588.00		
1050 51208	UTILITY PIPE, F&I, DI/CI, WATER / SEWER, 8"	LF	101.00		
1055 51106	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, F&I, ELBOW 6"	EA	54.00		
1055 51108	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, F&I, ELBOW 8"	EA	6.00		
1055 51112	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, F&I, ELBOW 12"	EA	12.00		
1055 51208	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, F&I, TEE 8"	EA	4.00		
1055 51212	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, F&I, TEE 12"	EA	15.00		
1055 51308	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, F&I, REDUCER 8"	EA	3.00		
1055 51312	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, F&I, REDUCER 12"	EA	2.00		
1055 51508	UTILITY FITTINGS, DI/CI F&I, CAP/PL, 8"	EA	2.00		
1055 51612	UTILITY FITTINGS, DI/CI F&I, CROSS, 12"	EA	1.00		
1060 11211	UTILITY STRUCTURE, BELOW GROUND, F&I, WATER /SEWER, 0- 80 FT3, 0	EA	2.00		
1060 11222	UTILITY STRUCTURE, BELOW GROUND, F&I, WATER /SEWER > 80 FT3, 6.1	EA	4.00		
1060 16	UTILITY STRUCTURE, BELOW GROUND, REMOVE & DISPOSE	EA	4.00		
1070 1 10	UTILITY AUXILIARY ITEMS, SIGN UP TO 12 SF	EA	10.00		
1080 21106	UTILITY FIXTURE, VALVE/METER BOX, F&I, 6"	EA	15.00		
1081 21108	UTILITY FIXTURE, VALVE/METER BOX, F&I, 8"	EA	6.00		
1082 21112	UTILITY FIXTURE, VALVE/METER BOX, F&I, 12"	EA	7.00		
1080 23101	UTILITY FIXTURES, TAPPING SADDLE / SLEEVE, F&I, 1.5"	EA	48.00		

1080 23106	UTILITY FIXTURES, TAPPING SADDLE / SLEEVE, F&I, 6"	EA	2.00		
1080 24106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	15.00		
1080 24108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	EA	6.00		
1080 24112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	7.00		
1080 26106	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 6"	EA	1.00		
1080 26112	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 12"	EA	1.00		
1080 29106	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, F&I, 6"	EA	69.00		
1080 29108	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, F&I, 8"	EA	16.00		
1081 29112	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, F&I, 12"	EA	21.00		
1080 32102	UTILITY FIXTURES, SAMPLE POINT, F&I, 2"	EA	13.00		
1644112 08	FIRE HYDRANT, F&I, STANDARD, 2 HOSE, 6"	EA	13.00		
1644900	FIRE HYDRANT, REMOVE	EA	6.00		
				TOTAL =	